

THE CORPORATION OF THE TOWN OF AMHERSTBURG

BY-LAW NO. 2021 – 016

By-law to provide for the Improvements to the Charles Shepley Drain based on  
the Drainage Report by R. Dobbin Engineering Inc.

---

**WHEREAS** a request for improvement of the Charles Shepley Drain was received under section 78 of the Drainage Act;

**WHEREAS** Council of the Corporation of the Town of Amherstburg appointed an engineer for the purpose of preparation of an engineer's report for the improvements of the Charles Shepley Drain under section 78 of the Drainage Act;

**WHEREAS** Council of the Corporation of the Town of Amherstburg has authorized Mike Gerrits, P. Eng., to prepare a report and said engineer's report dated January 18, 2021, can be referenced as Schedule A, as attached hereto;

**WHEREAS** \$73,336.00 is the estimated cost of improving the drainage works;

**AND WHEREAS** the report was considered by the Amherstburg Drainage Board at the meeting held on March 2, 2021.

**NOW THEREFORE** the Council of the Corporation of the Town of Amherstburg hereby enacts as follows:

**1. AUTHORIZATION**

The attached report is adopted and the drainage works is authorized and shall be completed as specified in the report

**2. BORROWING**

The Corporation of the Town of Amherstburg may borrow on the credit of the Corporation the amount of \$73,336.00 being the amount necessary for the improvements of the drainage works.

**3. DEBENTURE(S)**

The Corporation may issue debenture(s) for the amount borrowed less the total amount of:

- (a) Grants received under section 85 of the Drainage Act;
- (b) Monies paid as allowances;
- (c) Commuted payments made in respect of lands and roads assessed with the municipality;
- (d) Money paid under subsection 61(3) of the Drainage Act; and
- (e) Money assessed in and payable by another municipality.

**4. PAYMENT**

Such debenture(s) shall be made payable within 5 years from the date of the debenture(s) and shall bear interest at a rate not higher than 1% more than the municipal lending rates as posted by The Town of Amherstburg's Bank's Prime Lending Rate on the date of sale of such debenture(s).

(1) A special equal annual rate sufficient to redeem the principal and interest on the debenture(s) shall be levied upon the lands and roads and shall be collected in the same manner and at the same as other taxes are collected in each year for 5 years after the passing of this by-law.

(2) All assessments of \$1000.00 or less are payable in the first year in which the


assessments are imposed.

Read a first and second time and provisionally adopted this 8<sup>th</sup> day of March, 2021.

  
\_\_\_\_\_  
MAYOR – ALDO DICARLO

  
\_\_\_\_\_  
CLERK – PAULA PARKER

Read a third time and finally passed this 24 day of Jan. 2021. 2022

  
\_\_\_\_\_  
MAYOR – ALDO DICARLO

  
\_\_\_\_\_  
CLERK – PAULA PARKER  
 Deputy Clerk – Tammy Fawkes

December 7, 2021

(Revised to include June 1, 2021 COR Decision and November 10, 2021 Tribunal Decision)

Original Report - January 18, 2021

The Mayor and Council  
Town of Amherstburg  
271 Sandwich Street South  
Amherstburg, Ontario  
N9V 2A5

Gentlemen and Mesdames:

**Re: Charles Shepley Drain**

As instructed, we have undertaken an examination of the Charles Shepley Main Drain and Charles Shepley Branch Drain with regards to an investigation of existing culverts and drain maintenance schedules.

Authorization under the Drainage Act

This Engineers Report has been prepared under Section 78 of the Drainage Act as per the request of an affected landowner.

Section 78 of the Drainage Act states that, where, for the better use, maintenance or repair of any drainage works constructed under a bylaw passed under this Act, or of lands or roads, it is considered expedient to change the course of the drainage works, or to make a new outlet for the whole or any part of the drainage works, or to construct a tile drain under the bed of the whole or any part of the drainage works as ancillary thereto, or to construct, reconstruct or extend embankments, walls, dykes, dams, reservoirs, bridges, pumping stations, or other protective works as ancillary to the drainage works, or to otherwise improve, extend to an outlet or alter the drainage works or to cover the whole or any part of it, or to consolidate two or more drainage works, the Council whose duty it is to maintain and repair the drainage works or any part thereof may, without a petition required under Section 4 but on the report of an Engineer appointed by it, undertake and complete the drainage works as set forth in such report.

### Existing Drainage – Charles Shepley Main Drain

Two reports have been authored on the Charles Shepley Main Drain. The first report was by W. Settingington and was dated June 1968. The second report was prepared by M. Armstrong and was dated July 1980.

The existing drainage works consists of approximately 3,786 metres of open channel that outlets into the Long Marsh Drain in Lot 100, Concession 9. The drain extends approximately 1,813 m from the outlet in a southerly direction along the west side of Smith Road until the south side of Malden Colchester South Townline (Concession Road 4). The drain then extends approximately 1,890m in a westerly direction until the east side of Malden Colchester Townline (Concession Road 7) where it then extends approximately 72 m in a southerly direction until the northern limit of the lands identified with the Land Identification Number 19 in Part of Lot 1 Concession 3, Town of Essex.

The existing drain reports identified the following culverts.

Culvert 2– The culvert is located at Station 0+450 on the plan. The culvert provides access to the lands identified with the Land Identification Number 2 (Pt of Lot 101 Concession 9, Town of Amherstburg).

Culvert 3– The culvert is located at Station 1+153 on the plan. The culvert provides access to the lands identified with the Land Identification Number 6 (Pt of Lot 102 Concession 9, Town of Amherstburg).

Culvert 4– The culvert is located at Station 1+236 on the plan. The culvert provides access to the lands identified with the Land Identification Number 8 (Pt of Lot 102 Concession 9, Town of Amherstburg).

Culvert 5– The culvert is located at Station 1+813 on the plan. The culvert is a Malden Colchester South Townline centreline road culvert. The 1980 report identifies a bridge at this location.

Culvert 6 - The culvert is located at Station 2+751 on the plan. The culvert provides access to the lands identified with the Land Identification Number 22 (Pt of Lot 2 Concession 3, Town of Essex).

Culvert 7 - The culvert is located at Station 3+025 on the plan. The culvert provides access to the lands identified with the Land Identification Number 21 (Pt of Lot 1 Concession 3, Town of Essex).

There are two culverts on this drain that are not identified in either of the drain reports.

Culvert 1- The culvert is located at Station 0+135 on the plan. The culvert provides access to the lands identified with the Land Identification Number 1 (Pt of Lot 100 Concession 9, Town of Amherstburg).

Pedestrian Culvert (3+389) – The pedestrian culvert is located at Station 3+389 on the plan. The culvert provides access to the lands identified with the Land Identification Number 20 (Pt of Lot 1 Concession 3, Town of Essex).

The land identified with the Land Identification Number 8 does not currently have an access across the Charles Shepley Main Drain. The property is accessed from Concession Road 9 and a culvert on the Charles Shepley Branch Drain.

The lands identified with the Land Identification Numbers 3 and 4 do not have an access across the Charles Shepley Main Drain and utilize Culvert 2 to access their lands.

The lands identified with the Land Identification Numbers 24, 26 and 30 not have an access across the Charles Shepley Main Drain. The properties are accessed from Concession Road 3.

#### Existing Drainage – Charles Shepley Branch Drain

Two reports have been authored on the Charles Shepley Branch Drain. The first report was by W. Settington and was dated June 1969. The second report was prepared by M. Armstrong and was dated July 1980.

The existing drainage works consists of approximately 990 metres of open channel that is located in the Town of Amherstburg and outlets into the Charles Shepley Main Drain at the easterly limit of Lot 102, Concession 9. The drain extends in a westerly direction along the north limit of the South ½ of Lot 102, Concession 9 for approximately 675 m after which it extends southerly for 315 m to the north limit of Lot 103, Concession 9.

The 1980 report identified one access culvert on the Charles Shepley Branch Drain at Station 4+832. The culvert was removed prior to this report.

There are three crossings on this drain that are not identified in the drain report.

Culvert 8 – The culvert is located at Station 4+385 on the plan. The culvert provides access between the land identified with the Land Identification Number 8 (Pt of the South ½ of Lot 102 Concession 8) and the land identified with the Land Identification Number 5 (Pt of the North ½ of Lot 102 Concession 8). Both lands are currently owned by the same landowner. The culvert does not front onto a Municipal road.

Farm Access Culvert (4+684) – The culvert is located at Station 4+684 on the plan. The culvert provides access across the Charles Shepley Branch Drain for the land identified with the Land Identification Number 7 (Part of Lot 100 Concession 9, Town of Amherstburg).

Culvert 9 – The culvert is located at Station 4+983 on the plan. The culvert provides access across the Charles Shepley Branch Drain for the land identified with the Land Identification Number 7 (Pt of Lot 100 Concession 9, Town of Amherstburg).

The drain has accumulated sediment throughout and the field tiles are located at the bottom of the channel at the top of the sediment. The existing culverts were not installed to the design grade line.

#### Drain Classification

The Charles Shepley Main Drain and the Charles Shepley Branch Drain are classified as a Class “F” drain. These classifications are according to the Ontario Ministry of Agriculture, Food and Rural Affairs’ Agricultural Information Atlas.

Class “F” drains are intermittent or ephemeral (dry for more than two consecutive months). Authorization is not required if work is done in the dry.

The proposed work will have very little effect on the drainage works if carried out during low flows in the channel. The work area is to be maintained in a dry condition during construction by the Contractor.

The Essex Region Conservation Authority (ERCA) reviewed and approved the project via email correspondence. A copy of the approvals (November 25, 2020 email) has been included in Appendix A.

The Department of Fisheries and Oceans Canada reviewed and approved the project. A copy of the Department of Fisheries and Oceans Canada Letter of Advice dated December 21, 2020 has been included in Appendix A.

#### Onsite Meeting and Landowner Correspondence

An onsite meeting was held on March 7, 2019 at #10596 Smith Road. The following attended the meeting.

Shane McVitty – The Corporation of the Town of Amherstburg  
Josh Warner – R. Dobbin Engineering  
Mike Gerrits – R. Dobbin Engineering  
Alen Beetham – Landowner  
Janet Labrecque – Landowner  
Chris Beaune – Landowner

A brief summary of the meeting is listed below:

- The Corporation of the Town of Amherstburg received a request for a bridge repair on the Charles Shepley Drain from M. & A. Beetham (Landowner Identification Number 1) whom own Part of Lot 100, Concession 9. Upon investigation it was noted the bridge was not part of a report and as such a report was required.
- ERCA has forwarded comments. The design will need to maintain flood elevations up to and including the 100-year storm event. It will also need to account for ice damming. A 2400 mm concrete box culvert was recently installed upstream of the crossing.
- Maintenance schedule updates will also be included in the new report.
- C. Beaune (Identification Number 4) cannot safely back vehicles and equipment across the Charles Shepley Main Drain. C. Beaune feels the Smith Road is too narrow and has requested a larger culvert. R. Dobbin Engineering Inc. will review the entrance and determine if the road width affects turning movements.
- R. Dobbin Engineering Inc. inspected the Beaune access and note the road width was approximately 7 m with narrow shoulders. It was clear the landowner utilized the entire road platform plus the road embankment to back equipment and vehicles across the Charles Shepley Main Drain.

Prior to issuing this report, R. Dobbin Engineering Inc. contacted the following landowners to discuss the drain grades and culverts.

A. Beetham – The Beetham's own the lands identified by the Landowner Identification Numbers 1,2, 3 and 4. The four properties are serviced by two access culverts. A. Beetham requested Culvert 1 be relocated from Station 0+153 to the southern limit of the property at Station 0+258. The landowner did not want culverts installed to each property nor did he want future replacement specifications incorporated into this report.

C. Beaune – C. Beaune requested the access to his land have a minimum top width equal to the existing culvert plus 1.83m (6 feet). The landowner is aware the costs to lengthen the culvert will be assessed as a benefit to his lands.

J. Grondin (Identification Number 26) – J. Grondin contacted R. Dobbin Engineering Inc. to discuss the Charles Shepley Branch Drain. J. Grondin feels Culvert 8 is an obstruction and needs to be removed or lowered at the landowner's expense. J. Grondin also mentioned the tiles are at the bottom of the channel and do not have a sufficient outlet. M. Gerrits of R. Dobbin Engineering Inc. informed J. Grondin a survey of the drain would be completed and determined if the culvert is an obstruction. The status and condition of the culvert will also be looked into. J. Grondin can access his lands identified with the Land Identification Number 7 (Part of Lot 100 Concession 9, Town of Amherstburg) without crossing over the drain and has informed R. Dobbin Engineering Inc. that he does not require Culvert 9. Culvert 9 has been included in this report for future replacement if there is a change in ownership of the adjacent lands or if the landowner requests the culvert be installed.

F. Miller (Identification Number 20) – F. Miller of Miller Cattle and Grain Ltd. confirmed he would like the pedestrian crossing at Station 3+389 removed and a new access installed at Station 3+786. The landowner requested the ditch be filled in as a culvert was not required. R. Dobbin Engineering Inc. reviewed the crossing and determined the ditch could be filled in to provide the landowner with an access across the Charles Shepley Main Drain.

Bonnefield Farmland Ontario (Identification Numbers 5 & 8) – Bonnefield Farmland Ontario confirmed they wanted to keep the access across the Charles Shepley Branch Drain at Station 4+385 (Culvert 8). The culvert is perched and will be replaced in the future under maintenance.



### Design

The proposed residential access culverts will be sized to convey a minimum 2-year design storm. The Municipal road culvert will be designed to convey a minimum 25-year design storm. In order to meet the ERCA requirements the proposed culvert diameters and flow rates will not be reduced.

R Dobbin Engineering Inc. has reviewed the C. Beaune access culvert, Culvert 3, with respect to the Smith Road width, road side ditching and the proximity of the Charles Shepley Main Drain. Smith Road has a 7.0 m paved width with minimal shoulders. When considering the cross section of Smith Road, R Dobbin Engineering Inc. feels the minimum top width for accesses that front onto Municipal Roads should be increased from the standard 6.0 m to 8.5 m to provide safe access to the property. The minimum top width for accesses that do not front onto a Municipal road allowances will remain 6.0 m.

### Discussion

Culvert (Station 0+153) – The culvert located on the Charles Shepley Main Drain in Pt. of the Lot 100, Concession 9 (Land Identification Number 1) consists of 7.0 m of a 2000 mm dia. CSP with concrete bag headwalls and is located at Station 0+135. The pipe is in very poor condition. The pipe is to be replaced under this report with 10.5 m of 2200 mm dia. CSP culvert to account for the minimum top width of 8.5 m with concrete block end walls. The landowner has requested the access be moved to the southerly limit of his farm at Station 0+258.

Culvert 2 – The culvert located on the Charles Shepley Main Drain in Pt. of the Lot 101, Concession 9 (Land Identification Number 2) consists of 7.0 m of a 2400 mm X 2400 mm concrete box culvert. The culvert immediately upstream is a 1600 mm dia. CSP and the culvert downstream is a 2000mm dia. CSP. The concrete box culvert is in good condition. In the future, the culvert will be replaced with a 2400 mm X 2400 mm concrete box culvert of similar length unless the approval authorities permit an equivalent CSP or a smaller 2200 mm dia. CSP since the flows are governed by both the upstream and downstream culverts. The replacement culvert can be lengthened to 10.5 m to account for the minimum top width of 8.5 m with concrete block end walls.

Culvert 3 – The culvert located on the Charles Shepley Main Drain in Pt. of the Lot 102, Concession 9 (Land Identification Number 6) consists of 8.0 m of a 1200 mm CSP with concrete bag headwalls. The pipe is in very poor condition. The pipe is to be replaced under this report with 12 m of 1600 mm dia. CSP culvert to account for the minimum top width of 8.5 m with concrete block end walls.

Culvert 4 – The culvert located on the Charles Shepley Main Drain in Pt. of the Lot 102, Concession 9 (Land Identification Number 8) consists of 6.0 m of a 1200 mm CSP with concrete bag headwalls. The pipe is in poor condition. In the future the pipe shall be replaced with 10.5 m of 1600 mm dia. CSP culvert to account for the minimum top width of 8.5 m with concrete block end walls.

Culvert 5 – The culvert is located on the Charles Shepley Main Drain in the Malden Colchester South Townline road Allowances and consists of 28 m of a 2200 mm CSP with rip rap end protection. The pipe is in good condition. In the future the culvert shall be replaced with 28.0 m of 2200 mm dia. CSP with rip rap end protection.

Culvert 6 – The culvert is located on the Charles Shepley Main Drain in Pt. of the Lot 2, Concession 3 (Land Identification Number 22) consists of 18.0 m of a 1200 mm concrete pipe with rip rap end walls. The pipe is in good condition. In the future the pipe shall be replaced with 18.0 m of 1400 mm dia. CSP culvert to account for the minimum top width of 8.5 m, 5.0 m lawn enclosure with rip rap end protection.

Culvert 7 – The culvert is located on the Charles Shepley Main Drain in Pt. of the Lot 1, Concession 3 (Land Identification Number 21) consists of 8.0 m of a 900 mm CSP pipe with rip rap end walls. The pipe is in good condition. In the future the pipe shall be replaced with 10.0 m of 1000 mm dia. CSP culvert to account for the minimum top width of 8.5 m with concrete block end walls.

Culvert 8 – The culvert is located on the Charles Shepley Branch Drain in Pt. of the South ½ of Lot 102 Concession 8 (Land Identification Number 8) is 10.0 m in length and consists of a CSP culvert with 760 mm dia. High Density Polyethylene (HDPE) culvert extensions. The culvert is in poor condition and is perched. In the future the pipe shall be replaced with 10.5 m of 750 mm dia. HDPE culvert to account for the minimum top width of 6.0 m with rip rap end protection.

Culvert 9 – The culvert is located on the Charles Shepley Branch Drain in Pt. of Lot 100 Concession 9 (Land Identification Number 7) consists of 6.0 m of a 400 mm CSP pipe. In the future the pipe shall be replaced with 10.0 m of 450 mm dia. HDPE pipe culvert to account for the minimum top width of 6.0 m with rip rap end protection.

Farm Access (Station 3+389) – The culvert is located on the Charles Shepley Main Drain in Pt. of the Lot 1, Concession 3 (Land Identification Number 20) consists of 2.0 m of a 900 mm CSP culvert with concrete bag headwalls. The pipe is very short and will be removed under this report and the affected lands will be accessed by a new access at Station 3+786. The new access is at the top end of the drain and will included filling in the existing ditch since a culvert is not required. No subsurface drainage was observed during the survey. Once the access is constructed the portion of the drain between Station 3+780 and 3+810 shall be abandoned as it is not longer required.

Farm Access (4+684) – The culvert is located on the Charles Shepley Branch Drain at Station 4+684 on the plan. The culvert provides access across the drain for the land identified with the Land Identification Number 7 (Part of Lot 100 Concession 9, Town of Amherstburg). The culvert is considered a secondary culvert and will be removed from the drain when maintenance is competed on the drain by the Landowner or the Contractor retained to complete maintenance.

### Recommendations

It is therefore recommended that the following work be carried out:

1. Remove the culvert at Station 0+135 and restore the crossing to its design cross section complete with the placement of topsoil and seed on all disturbed areas including the bank.
2. Install a new access culvert, Culvert 1 in Pt. of the Lot 100, Concession 9 (Land Identification Number 1) with 10.5 m of 2200 mm dia. corrugated steel pipe culvert with concrete block end walls.
3. Remove and replace Culvert 3 in Pt. of the Lot 102, Concession 9 (Land Identification Number 6) with 12 m of 1600 mm dia. corrugated steel pipe culvert concrete block end walls.
4. Remove the culvert at Station 3+389 and restore the crossing to its design cross section complete with the placement of topsoil and seed on all disturbed areas including the bank.

5. Construct a new access at Station 3+786 by filling in the ditch. A culvert is not required at this location. Once the access is constructed the portion of the drain between Station 3+780 and 3+810 shall be abandoned as it is not longer required.

#### Estimate of Cost

It is recommended that the work be carried out in accordance with the accompanying Specification of Work and the profile, which form part of this Report. There has been prepared an Estimate of Cost in the amount of \$73,336.00, including the cost of engineering. A plan has been prepared showing the location of the work and the approximate drainage area.

#### Assessment

As per Section 21 of the Drainage Act, the Engineer in his report shall assess for benefit and outlet for each parcel of land and road liable for assessment.

Lands, roads, buildings, utilities, or other structures that are increased in value or are more easily maintained as a result of the construction, improvement, maintenance, or repair of a drainage works may be assessed for benefit. (Section 22)

Lands and roads that use a drainage works as an outlet, or for which, when the drainage works is constructed or improved, an improved outlet is provided either directly or indirectly through the medium of any other drainage works or of a swale, ravine, creek, or watercourse may be assessed for outlet. The assessment for outlet shall be based on the volume and rate of flow of the water artificially caused to flow into the drainage works from the lands and roads liable for such assessments. (Section 23)

The Engineer may assess for special benefit any lands for which special benefits have been provided by the drainage works. (Section 24)

A Schedule of Assessment for lands and roads affected by the work and therefore liable for the cost thereof has been prepared as per the Drainage Act. Any affected public utility or road authority shall be assessed, as per Section 26 of the Drainage Act, any increased costs for the removal or relocation of any of its facilities and plant that may be necessitated by construction or future maintenance and repair work. The cost of any fees for permits or approvals or any extra work required by any affected utility or road authority shall be assessed to that organization requiring the permit, approval, or extra

work. Items to be assessed under Section 26 shall be tendered separately with the actual cost plus a portion of the engineering (25% of the cost).

1. Culvert 1 has been assessed with 41% of the cost applied as benefit assessment to the landowner of the property and the remainder of the cost assessed as an outlet assessment on upstream lands and roads based on equivalent hectares.
2. Culvert 3 has been assessed with 8.5 metres of the culvert and concrete block end walls assessed with 51% of the cost applied as benefit assessment to the landowner of the property and the remainder of the cost assessed as an outlet assessment on upstream lands and roads based on equivalent hectares. The remainder of the costs has been assessed as a benefit assessment to the landowner of the property for the additional length of culvert beyond the 8.5 m standard access top width.
3. Farm Access (Station 3+786) has been assessed with 9.5 metres of the ditch infilling and end protection assessed with 62% of the cost applied as benefit assessment to the landowner of the property and the remainder of the cost assessed as an outlet assessment on upstream lands and roads based on equivalent hectares. The remainder of the ditch that is filled in has been assessed as a benefit assessment to the landowner of the property for the additional length of infilling beyond the 8.5 m standard access top width.
4. Future culvert replacement engineering costs have generally been assessed as follows:

Description	Benefit Assessment Landowner(s)	Outlet Assessment
Culvert 2	41%	59%
Culvert 4	51%	49%
Culvert 5	100%	
Culvert 6	58%	42%
Culvert 7	62%	38%
<b>Culvert 8</b>	<b>100%</b>	
Culvert 9	50%	50%

**\*\*Culvert 8 revised as per the November 10, 2021 Tribunal Decision\*\***

The outlet portion of the assessment is assessed to upstream lands and roads based on equivalent hectares.

5. Updating the Maintenance Schedules for each drain has been assessed with 100% of the costs applied as an outlet assessment on upstream lands and roads based on equivalent hectares.

The report includes the following Schedules of Assessments tables.

*Schedule of Assessment – Charles Shepley Main Drain*

The Schedule of Assessment includes the removal of existing culverts at Station 0+135 and Station 3+389, the installation of Culvert 1 at Station 0+258, installation of Culvert 3 at Station 1+153, construction of the access at Station 3+786, future culvert engineering costs, updating the Schedule of Maintenance and updating the Main Drain specifications.

*Schedule of Assessment – Charles Shepley Branch Drain*

The Schedule of Assessment includes future culvert engineering costs, updating the Schedule of Maintenance and updating the Branch Drain specifications.

*Composite Schedule of Assessment – Charles Shepley Main and Branch Drains*

The Composite Schedule of Assessment is a summary of total assessment and is calculated by combining each landowner's assessment from the Main Drain and Branch Drain.

Allowances

Under Section 30 of the Drainage Act, the Engineer shall determine the amount to be paid to persons entitled thereto to damage, if any, to ornamental trees, fences, land, and crops occasioned by the disposal of material removed from a drainage works. This shall be considered an allowance for damages. Section 30 allowances will be provided under this report.

Access and Working Area

Access to the work site shall be gained from road allowances when possible, along existing private lanes and along the fence lines. Access to the drainage works shall be supplied through each property. Access to the working area along the private lanes and fence lines shall be restricted to a width of 6.0 m.

The working area shall be on the same side of the drain on which the excavated material is disposed of. The working corridor is 10.0 m. The working corridor will be measured from the adjacent finished top of bank.

Access for culvert installation or replacements shall be from the property which the culvert is located in. The access shall be along the property line or as agreed to by the landowner. When possible, maintenance should be completed when crops are off.

The working area around culverts shall extend to 12m from the adjacent finished top of bank on each side of the drain for a distance of 20.0 m upstream and downstream of the culvert.

The excavated earth from Station 0+000 to Station 1+813 shall be cast onto the adjacent lands to the west. From Station 1+813 to 3+786 the excavated material shall be cast onto the adjacent lands to the east and south. When a drain passes in front of any house, lawn, garden driveway orchard etc. the excavated material shall be hauled away and spread upon the adjoining lands or as directed by the Drainage Superintendent. The Contractor will be required to haul material more than 150m.

The excavated earth from Station 4+000 to Station 4+684 (Charles Shepley Branch Drain) shall be cast onto the adjacent lands to the south. From Station 4+684 to 4+983 the excavated material shall be cast onto the adjacent lands to the east.

#### Restrictions

No trees and shrubs shall be planted nor shall permanent structures be erected within 10 m of either side of the proposed drain without prior written permission of Council. If trees are planted that interfere with access for future maintenance of the drainage works, they shall be removed at the expense of the landowner.

Attention is also drawn to Sections 80 and 82 of the Drainage Act that refers to the obstruction of a drainage works.

#### Agricultural Grant

Agricultural Grants are determined by OMAFRA's ADIP policies and are not included in this report. It is recommended that application for subsidy be made for eligible agricultural properties be made on behalf of the eligible Landowners. Any assessments against non agricultural properties are shown separately in the Schedule of Assessment. R. Dobbin Engineering Inc. contacted the landowner who will be assessed a benefit on Culvert 8 and informed them the culvert may not be eligible for grant. The Culvert 8 assessments reflect this assumption.

### Maintenance

Upon completion of the work, the open channel drainage works shall be maintained as per the applicable Schedules of Maintenance and the specifications enclosed with this report unless otherwise altered under the provisions of the Drainage Act or as outlined below.

#### *Schedule of Maintenance Charles Shepley Main Drain – Section 1*

This Schedule of Maintenance includes the work completed between Station 0+000 (Outlet to the Long Marsh Drain) and to Station 1+824 (4<sup>th</sup> Concession Road). Culverts are to be maintained in accordance with the following culvert maintenance table.

#### *Schedule of Maintenance Charles Shepley Main Drain – Section 2*

This Schedule of Maintenance includes the work completed between Station 1+824 (Intersection of Smith Road and 4<sup>th</sup> Concession Road). Culverts are to be maintained in accordance with the following culvert maintenance table.

#### *Schedule of Maintenance Charles Shepley Branch Drain – Section 1*

This Schedule of Maintenance includes the work completed between Station 4+000 (Outlet to the Charles Shepley Main Drain) and to Station 4+990. Culverts are to be maintained in accordance with the following culvert maintenance table.

The standard culvert length for culverts that front onto road allowances shall be based on an 8.5 m top width plus the length required for concrete block end walls or rip rap end protection. The standard culvert length for all other culverts shall be based on a 6.0 m top width plus the length required for rip rap end protection. The rip rap shall be placed with a backslope of 1.5 H:1.0 V. If a landowner requests an additional length of culvert beyond the standard width the extra cost shall be borne by the landowner making the request including the future maintenance and repair.



The cost to maintain the standard culvert length shall be assessed as follows, cost beyond the standard length will be assessed to the benefiting landowner:

Culvert Maintenance Table

Station	Description	Benefiting Landowner(s)	Benefit Assessment Landowner(s)	Outlet Assessment
0+258	Culvert 1	1	41%	59%
0+450	Culvert 2	2	41%	59%
1+153	Culvert 3	6	51%	49%
1+236	Culvert 4	8	51%	49%
1+813	Culvert 5	Town of Amherstburg Town of Essex	50% 50%	
2+751	Culvert 6	22	58%	42%
3+025	Culvert 7	21	62%	38%
4+385	Culvert 8 - Removal of Private Culvert	5/8	50% Each	
4+385	Culvert 8 - Installation	5/8	50% Each	
4+684	Private Culvert	7	100%	
4+983	Culvert 9	7	50%	50%

**\*\*Culvert 8 revised as per the November 10, 2021 Tribunal Decision\*\***

Each property is allowed one access culvert for each municipal drain with any second culvert on the property maintained and repaired 100% by the landowner.

The report includes the following Schedules of Maintenance

These above conditions will apply unless otherwise altered under the provisions of the Drainage Act.

All of the above is submitted for your consideration.

Yours truly,

  
Jan 14, 2021  
2019-1021

Mike Gerrits, P. Eng.  
R. Dobbin Engineering Inc.



Charles Shepley Drain  
 Town of Amherstburg  
 January 18, 2021

### ALLOWANCES

Allowances have been made as per Section 30 of the Drainage Act for damages to lands and crops including for future maintenance operations.

Conc.	Lot or part	Owner I.D. Number	Owner	Section 30 (\$)	Total (\$)
<u>Charles Shepley Main Drain</u>					
9	Pt Lot 100	1	A. & K. Beetham	100	100
	Pt Lot 102	6	P. McFadden & C. Beaune	100	100
3	Pt Lot 1	20	Miller Cattle and Grain Ltd.	100	100
			Total Allowances	\$ 300	\$ 300

Charles Shepley Drain  
Town of Amherstburg  
January 18, 2021

**ESTIMATE OF COST  
CHARLES SHEPLEY MAIN DRAIN & BRANCH DRAIN**

	Quantity	Unit	Material (\$)	Labour (\$)	Total (\$)
<u>Main Drain</u>					
Allowances:					300
<b>Culvert (Station 0+135)</b>					
Removal of Existing 2000mm dia. CSP Structure and Headwalls and Restore Channel	1	L.S.	250	660	910
<b>Culvert 2 (Station 0+258)</b>					
Supply & Install 2200mm dia CSP c/w Bedding Material	11	m	6,006	4,400	
Supply and Install Backfill Material	100	t	1,000	1,120	
Granular 'A'	37	t	555	463	
Concrete Block End Walls	32	Blocks	2,560	1,600	
Restoration	1	LS	500	500	18,704
<b>Culvert 3 (Station 1+153)</b>					
Removal of Existing 1200mm dia. CSP Structure and Headwalls	1	L.S.	100	220	
Remove and Reinstall Mail Box	1	L.S.	-	250	
Supply & Install 1600mm dia CSP c/w Bedding Material	12.0	m	5,232	3,960	
Supply & Install Backfill Material	110	t	1,100	1,280	
Granular 'A'	40	t	600	500	
Concrete Block End Walls	32	Blocks	2,560	1,600	
Restoration	225	sq.m.	563	563	18,528

Estimate of Costs (cont'd)  
(Charles Shepley Drain)

	Quantity	Unit	Material	Labour	Total
<b>Culvert (Station 3+389)</b>					
Removal of Existing 900mm dia CSP Pedestrian Crossing Structure and Headwalls and Restore Channel	1	L.S.	100	220	320
<b>Farm Assess 8 (Station 3+786)</b>					
Strip Existing Ditch	1	L.S.	-	250	
Fill Ditch with Imported Material	61	t	458	305	
Granular 'A'	20	t	300	250	
Rip Rap	15	sq.m.	375	375	
Restoration	1	L.S.	250	250	2,813
<b>Sub Total</b>					<b>41,575</b>
Miscellaneous					2,048
Engineering					11,263
Future Culvert Engineering					6,500
Update Schedules					4,000
ERCA Fee					800
<b>Estimated Cost Main Drain</b>					<b>\$ 66,186</b>
Non-Recoverable HST (1.76%)					1,146
<b>Total Estimated Cost Main Drain</b>					<b>\$ 67,332</b>
<u>Branch Drain</u>					
Future Culvert Engineering					4,543
Update Schedules					1,357
<b>Estimated Cost Branch Drain</b>					<b>\$ 5,900</b>
Non-Recoverable HST (1.76%)					104
<b>Total Estimated Cost Branch Drain</b>					<b>\$ 6,004</b>
<b>Total Estimate Charles Shepley Drain</b>					<b>\$ 73,336</b>

Charles Shepley Drain  
Town of Amherstburg  
January 18, 2021

**SCHEDULE OF ASSESSMENT  
CHARLES SHEPLEY MAIN DRAIN**

*Revised as per the Court of Revision (June 1, 2021)*

For the removal of existing culverts at Station 0+135 and Station 3+389, the installation of Culvert 1 at Station 0+258, installation of Culvert 3 at Station 1+153, construction of the access at Station 3+786, future culvert engineering costs, updating the Schedule of Maintenance and updating the Main Drain specifications.

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Special Benefit (\$)	Benefit (\$)	Outlet (\$)	Total (\$)
<b><u>Town of Amherstburg</u></b>								
<b>3. <u>Municipal Lands</u></b>								
	Malden Colchester S. Townline	2.4		Town of Amherstburg	-	650	970	1,620
	Malden Colchester Townline	0.1		Town of Amherstburg	-	-	104	104
	Smith Road	1.8		Town of Amherstburg	-	-	729	729
					-	650	1,803	2,453
				Total - Special Benefit	-			
				Total - Benefit	650			
				Total - Outlet		1,803		
				Total - Municipal Lands		2,453		
<b>4. <u>Privately-Owned Non-Agricultural Lands</u></b>								
7	Pt Lot 66	0.3	36	R. & D. Allen	-	-	208	208
9	Pt Lot 101	1.0	3	M. & A. Beetham	-	-	163	163
	Pt Lot 103	0.4	9	S. & K. Klomp	-	-	109	109
					-	-	480	480
				Total - Special Benefit	-			
				Total - Benefit	-			
				Total - Outlet		480		
				Total - Privately-Owned Non-Agricultural Lands		480		

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Special Benefit (\$)	Benefit (\$)	Outlet (\$)	Total (\$)
<b>5. Privately-Owned Agricultural Lands (Eligible for Available Grants)</b>								
9	Pt Lot 100	9.5	1	A. & K. Beetham	-	10,557	201	10,758
	Pt Lot 101	13.5	2	M. & A. Beetham	-	650	1,066	1,716
	Pt Lot 101	13.5	4	M. & A. Beetham	-	-	1,101	1,101
	Pt Lot 102	19.4	7	Grondin Farms Ltd	-	-	2,514	2,514
	Pt Lot 102	2.7	5	Bonnefield Farmland Ontario	-	-	216	216
	Pt Lot 102	1.1	6	P. McFadden & C. Beaune	-	14,140	86	14,226
	Pt Lot 102	16.0	8	Bonnefield Farmland Ontario	-	-	2,090	2,090
	Pt Lot 103	28.7	10	Grondin Farms Ltd	-	-	3,809	3,809
					-	25,347	11,083	36,430
				Total - Special Benefit	-			
				Total - Benefit	25,347			
				Total - Outlet	11,083			
				Total - Privately-Owned Agricultural Lands	36,430			
				Total - Special Benefit	-			
				Total - Benefit	25,997			
				Total - Outlet	13,366			
				Total - Town of Amherstburg	39,363			

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Special Benefit (\$)	Benefit (\$)	Outlet (\$)	Total (\$)
<b><u>Town of Essex</u></b>								
<b><u>3. Municipal Lands</u></b>								
	Smith Road	0.7		Town of Essex	-	-	343	343
	Malden Colchester S. Townline	2.4		Town of Essex	-	650	1,951	2,601
	Malden Colchester Townline	0.1		Town of Essex	-	-	176	176
					-	650	2,470	3,120
				Total - Special Benefit	-			
				Total - Benefit	650			
				Total - Outlet	2,470			
				Total - Municipal Lands	3,120			
<b><u>4. Privately-Owned Non-Agricultural Lands</u></b>								
3	Pt Lot 1	0.4	19	R. & M. Ferriss	-	-	328	328
	Pt Lot 2	0.3	25	J. & A. Brush	-	-	77	77
	Pt Lot 3	2.9	30	K. Pritchard & L. Roessler-Pritchar	-	-	385	385
	Pt Lot 3	0.4	34	A. Liser & M. Sahinidis	-	-	114	114
	Pt Lot 3	0.2	33	L. Pillon	-	-	45	45
	Pt Lot 3	1.6	32	K. Kimball	-	-	415	415
	Pt Lot 3	0.8	35	K. Kimball	-	-	202	202
	Pt Lot 3	0.7	29	M. Heleeji	-	-	184	184
	Pt Lot 3	0.2	28	R. & C. Shaw	-	-	53	53
	Pt Lot 3	0.4	27	F. Randall & J. Cooke	-	-	117	117
4	Pt Lot 3	1.9	18	H. Hepner	-	-	291	291
	Pt Lot 3	0.4	17	S. Scurk	-	-	115	115
					-	-	2,326	2,326
				Total - Special Benefit	-			
				Total - Benefit	-			
				Total - Outlet	2,326			
				Total - Privately-Owned Non-Agricultural Lands	2,326			

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Special Benefit (\$)	Benefit (\$)	Outlet (\$)	Total (\$)
<b>5. Privately-Owned Agricultural Lands (Eligible for Available Grants)</b>								
3	Pt Lot 1	13.8	20	Miller Cattle and Grain Ltd.	-	2,950	2,522	5,472
	Pt Lot 1	12.2	21	S. Zavaros	-	650	1,840	2,490
	Pt Lot 2	19.7	22	B. & N. Gorski	-	650	2,625	3,275
	Pt Lot 3	13.1	31	P. Rupert	-	-	1,742	1,742
	Pt Lot 3	18.5	26	J. Grondin	-	-	2,456	2,456
	Pt Lot 2	38.3	24	J. & A. Brush	-	-	5,096	5,096
	Pt Lot 2	6.1	23	L. McLean	-	-	806	806
4	Pt Lot 3	9.3	16	J. Drouillard	-	-	1,186	1,186
					-	4,250	18,273	22,523
				Total - Special Benefit	-			
				Total - Benefit	4,250			
				Total - Outlet	18,273			
				Total - Privately-Owned Agricultural Lands	22,523			
				Total - Special Benefit	-			
				Total - Benefit	4,900			
				Total - Outlet	23,069			
				Total - Town of Essex	27,969			
				Total - Town of Essex	27,969			
				Total - Town of Amherstburg	39,363			
				Total - Assessment	\$ 67,332			



Charles Shepley Drain  
Town of Amherstburg  
January 18, 2021

**SCHEDULE OF ASSESSMENT  
CHARLES SHEPLEY BRANCH DRAIN**

*Revised as per the Tribunal Decision dated November 10, 2021*

For the future culvert engineering costs, updating the Schedule of Maintenance and updating the Branch Drain specifications.

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Special Benefit (\$)	Benefit (\$)	Outlet (\$)	Total (\$)
<b><u>Town of Amherstburg</u></b>								
<b>5. Privately-Owned Agricultural Lands (Eligible for Available Grants)</b>								
9	Pt Lot 102	19.4	7	Grondin Farms Ltd	-	1,300	1,151	2,451
	Pt Lot 102	2.7	5	Bonnefield Farmland Ontario	-	975	-	975
	Pt Lot 102	12.0	8	Bonnefield Farmland Ontario	-	975	712	1,687
	Pt Lot 103	4.1	10	Grondin Farms Ltd	-	-	891	891
					-	3,250	2,754	6,004
				Total - Special Benefit	-			
				Total - Benefit	3,250			
				Total - Outlet		2,754		
				Total - Privately-Owned Agricultural Lands		6,004		
				Total Assessment	\$	6,004		

Charles Shepley Drain  
Town of Amherstburg  
January 18, 2021

**COMPOSITE SCHEDULE OF ASSESSMENT**  
**CHARLES SHEPLEY MAIN DRAIN & CHARLES SHEPLEY BRANCH DRAIN**  
*Revised as per the Tribunal Decision dated November 10, 2021*

The Composite Schedule of Assessment is a summary of total assessment and is calculated by combining each landowner’s assessment from the Main Drain and Branch Drain.

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Special Benefit (\$)	Benefit (\$)	Outlet (\$)	Total (\$)
<b><u>Town of Amherstburg</u></b>								
<b><u>3. Municipal Lands</u></b>								
	Malden Colchester S. Townline	2.4		Town of Amherstburg	-	650	970	1,620
	Malden Colchester Townline	0.1		Town of Amherstburg	-	-	104	104
	Smith Road	1.8		Town of Amherstburg	-	-	729	729
					-	650	1,803	2,453
				Total - Special Benefit	-			
				Total - Benefit	650			
				Total - Outlet	1,803			
				Total - Municipal Lands	2,453			
<b><u>4. Privately-Owned Non-Agricultural Lands</u></b>								
7	Pt Lot 66	0.3	36	R. & D. Allen	-	-	208	208
9	Pt Lot 101	1.0	3	M. & A. Beetham	-	-	163	163
	Pt Lot 103	0.4	9	S. & K. Klomp	-	-	109	109
					-	-	480	480
				Total - Special Benefit	-			
				Total - Benefit	-			
				Total - Outlet	480			
				Total - Privately-Owned Non-Agricultural Lands	480			

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Special Benefit (\$)	Benefit (\$)	Outlet (\$)	Total (\$)
<u>5. Privately-Owned Agricultural Lands (Eligible for Available Grants)</u>								
9	Pt Lot 100	9.5	1	A. & K. Beetham	-	10,557	201	10,758
	Pt Lot 101	13.5	2	M. & A. Beetham	-	650	1,066	1,716
	Pt Lot 101	13.5	4	M. & A. Beetham	-	-	1,101	1,101
	Pt Lot 102	19.4	7	Grondin Farms Ltd	-	1,300	3,665	4,965
	Pt Lot 102	2.7	5	Bonnefield Farmland Ontario	-	975	216	1,191
	Pt Lot 102	1.1	6	P. McFadden & C. Beaune	-	14,140	86	14,226
	Pt Lot 102	16.0	8	Bonnefield Farmland Ontario	-	975	2,802	3,777
	Pt Lot 103	28.7	10	Grondin Farms Ltd	-	-	4,700	4,700
					-	28,597	13,837	42,434
				Total - Special Benefit	-			
				Total - Benefit	28,597			
				Total - Outlet	13,837			
				Total - Privately-Owned Agricultural Lands	42,434			
				Total - Special Benefit	-			
				Total - Benefit	29,247			
				Total - Outlet	16,120			
				Total - Town of Amherstburg	45,367			

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Special Benefit (\$)	Benefit (\$)	Outlet (\$)	Total (\$)
<b><u>Town of Essex</u></b>								
<b><u>3. Municipal Lands</u></b>								
	Smith Road	0.7		Town of Essex	-	-	343	343
	Malden Colchester S. Townline	2.4		Town of Essex	-	650	1,951	2,601
	Malden Colchester Townline	0.1		Town of Essex	-	-	176	176
					-	650	2,470	3,120
				Total - Special Benefit	-			
				Total - Benefit	650			
				Total - Outlet	2,470			
				Total - Municipal Lands	3,120			
<b><u>4. Privately-Owned Non-Agricultural Lands</u></b>								
3	Pt Lot 1	0.4	19	R. & M. Ferriss	-	-	328	328
	Pt Lot 2	0.3	25	J. & A. Brush	-	-	77	77
	Pt Lot 3	2.9	30	K. Pritchard & L. Roessler-Pritchar	-	-	385	385
	Pt Lot 3	0.4	34	A. Liser & M. Sahinidis	-	-	114	114
	Pt Lot 3	0.2	33	L. Pillon	-	-	45	45
	Pt Lot 3	1.6	32	K. Kimball	-	-	415	415
	Pt Lot 3	0.8	35	K. Kimball	-	-	202	202
	Pt Lot 3	0.7	29	M. Heleeji	-	-	184	184
	Pt Lot 3	0.2	28	R. & C. Shaw	-	-	53	53
	Pt Lot 3	0.4	27	F. Randall & J. Cooke	-	-	117	117
4	Pt Lot 3	1.9	18	H. Hepner	-	-	291	291
	Pt Lot 3	0.4	17	S. Scurk	-	-	115	115
					-	-	2,326	2,326
				Total - Special Benefit	-			
				Total - Benefit	-			
				Total - Outlet	2,326			
				Total - Privately-Owned Non-Agricultural Lands	2,326			

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Special Benefit (\$)	Benefit (\$)	Outlet (\$)	Total (\$)
<u>5. Privately-Owned Agricultural Lands (Eligible for Available Grants)</u>								
3	Pt Lot 1	13.8	20	Miller Cattle and Grain Ltd.	-	2,950	2,522	5,472
	Pt Lot 1	12.2	21	S. Zavaros	-	650	1,840	2,490
	Pt Lot 2	19.7	22	B. & N. Gorski	-	650	2,625	3,275
	Pt Lot 3	13.1	31	P. Rupert	-	-	1,742	1,742
	Pt Lot 3	18.5	26	J. Grondin	-	-	2,456	2,456
	Pt Lot 2	38.3	24	J. & A. Brush	-	-	5,096	5,096
	Pt Lot 2	6.1	23	L. McLean	-	-	806	806
4	Pt Lot 3	9.3	16	J. Drouillard	-	-	1,186	1,186
					-	4,250	18,273	22,523
				Total - Special Benefit	-			
				Total - Benefit	4,250			
				Total - Outlet	18,273			
				Total - Privately-Owned Agricultural Lands	22,523			
				Total - Special Benefit	-			
				Total - Benefit	4,900			
				Total - Outlet	23,069			
				Total - Town of Essex	27,969			
				Total - Town of Essex	27,969			
				Total - Town of Amherstburg	45,367			
				Total - Assessment	\$ 73,336			

Charles Shepley Drain  
Town of Amherstburg  
January 18, 2021

**SCHEDULE OF MAINTENANCE - CHARLES SHEPLEY MAIN DRAIN**

**SECTION 1 - STATION 0+000 TO STATION 1+824**

*Revised as per the Court of Revision (June 1, 2021)*

For maintaining the open channel section of the Charles Shepley Drain between 0+000 (Outlet to the Long Marsh Drain) and Station 1+824 (4th Concession Road). The culverts are to be maintained in accordance with the culvert maintenance table in the maintenance section of the Report.

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Benefit (\$)	Outlet (\$)	Total (\$)	Equivalent Ha.
<b>Town of Amherstburg</b>								
<b>3. Municipal Lands</b>								
	Malden Colchester S. Townline	1.6		Town of Amherstburg	-	99	99	4.7
	Malden Colchester Townline	0.1		Town of Amherstburg	-	6	6	0.3
	Smith Road	1.8		Town of Amherstburg	2,250	56	2,306	7.1
<b>4. Privately-Owned Non-Agricultural Lands</b>								
7	Pt Lot 66	0.3	36	R. & D. Allen	-	11	11	0.5
9	Pt Lot 101	1.0	3	M. & A. Beetham	31	9	40	2.0
	Pt Lot 103	0.4	9	S. & K. Klomp	-	17	17	0.8
<b>5. Privately-Owned Agricultural Lands (Eligible for Available Grants)</b>								
9	Pt Lot 100	9.5	1	A. & K. Beetham	308	-	308	9.5
	Pt Lot 101	13.5	2	M. & A. Beetham	369	32	401	13.5
	Pt Lot 101	13.5	4	M. & A. Beetham	400	74	474	13.5
	Pt Lot 102	19.4	7	Grondin Farms Ltd	-	245	245	19.4
	Pt Lot 102	2.7	5	Bonnefield Farmland Ontario	200	24	224	2.7
	Pt Lot 102	1.1	6	P. McFadden & C. Beaune	229	11	240	1.1
	Pt Lot 102	16.0	8	Bonnefield Farmland Ontario	370	202	572	16.0
	Pt Lot 103	28.7	10	Grondin Farms Ltd	345	461	806	28.7
					4,502	1,247	5,749	
Total - Benefit					4,502			
Total - Outlet					1,247			
Total - Town of Amherstburg					5,749			

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Benefit (\$)	Outlet (\$)	Total (\$)	Equivalent Ha.
<b>Town of Essex</b>								
<b>3. Municipal Lands</b>								
	Malden Colchester S. Townline	2.4		Town of Essex	-	150	150	7.1
	Smith Road	0.7		Town of Essex	-	42	42	2.8
	Malden Colchester Townline	0.1		Town of Essex	-	9	9	0.4
<b>4. Privately-Owned Non-Agricultural Lands</b>								
3	Pt Lot 1	0.4	19	R. & M. Ferriss	-	17	17	0.8
	Pt Lot 2	0.3	25	J. & A. Brush	-	12	12	0.6
	Pt Lot 3	2.9	30	K. Pritchard & L. Roessler-Pritchard	-	61	61	2.9
	Pt Lot 3	0.4	34	A. Liser & M. Sahinidis	-	18	18	0.9
	Pt Lot 3	0.2	33	L. Pillon	-	7	7	0.3
	Pt Lot 3	1.6	32	K. Kimball	-	66	66	3.1
	Pt Lot 3	0.8	35	K. Kimball	-	32	32	1.5
	Pt Lot 3	0.7	29	M. Heleeji	-	29	29	1.4
	Pt Lot 3	0.2	28	R. & C. Shaw	-	8	8	0.4
	Pt Lot 3	0.4	27	F. Randall & J. Cooke	-	19	19	0.9
4	Pt Lot 3	1.9	18	H. Hepner	-	41	41	1.9
	Pt Lot 3	0.4	17	S. Scurk	-	13	13	0.8

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Benefit (\$)	Outlet (\$)	Total (\$)	Equivalent Ha.
<u>5. Privately-Owned Agricultural Lands (Eligible for Available Grants)</u>								
3	Pt Lot 1	13.8	20	Miller Cattle and Grain Ltd.	-	293	293	13.8
	Pt Lot 1	12.2	21	S. Zavaros	-	259	259	12.2
	Pt Lot 2	19.7	22	B. & N. Gorski	-	418	418	19.7
	Pt Lot 3	13.1	31	P. Rupert	-	278	278	13.1
	Pt Lot 3	18.5	26	J. Grondin	-	392	392	18.5
	Pt Lot 2	38.3	24	J. & A. Brush	-	812	812	38.3
	Pt Lot 2	6.1	23	L. McLean	-	129	129	6.1
4	Pt Lot 3	9.3	16	J. Drouillard	-	146	146	9.3
					-	3,251	3,251	
				Total - Benefit	-			
				Total - Outlet	3,251			
				Total - Town of Essex	3,251			
				Total - Town of Amherstburg	5,749			
				Total - Town of Essex	3,251			
				Total Assessment	\$ 9,000			



Charles Shepley Drain  
 Town of Amherstburg  
 January 18, 2021

**SCHEDULE OF MAINTENANCE - CHARLES SHEPLEY MAIN DRAIN  
 SECTION 2 - STATION 1+824 TO STATION 3+800**

*Revised as per the Court of Revision (June 1, 2021)*

For maintaining the section of the Charles Shepley Drain between Station 1+824 (Intersection of Smith Road and 4th Concession Road).  
 The culverts are to be maintained in accordance with the culvert maintenance table in the maintenance section of the Report.

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Benefit (\$)	Outlet (\$)	Total (\$)	Equivalent Ha.
<b><u>Town of Amherstburg</u></b>								
<b>3. <u>Municipal Lands</u></b>								
	Malden Colchester S. Townline	1.6		Town of Amherstburg	-	76	76	4.7
	Malden Colchester Townline	0.065		Town of Amherstburg	-	65	65	0.3
<b>4. <u>Privately-Owned Non-Agricultural Lands</u></b>								
7	Pt Lot 66	0.3	36	R. & D. Allen	-	120	120	0.5
9	Pt Lot 103	0.4	9	S. & K. Klomp	-	45	45	0.8
					-	306	306	
				Total - Benefit	-			
				Total - Outlet	306			
				Total - Town of Amherstburg	306			
<b><u>Town of Essex</u></b>								
<b>3. <u>Municipal Lands</u></b>								
	Malden Colchester S. Townline	2.4		Town of Essex	3,127	250	3,377	7.1
	Malden Colchester Townline	0.1		Town of Essex	213	45	258	0.4

Schedule of Maintenance Charles Shepley Main Drain (cont'd)  
 (Section 2 - Station 1+824 to Station 3+800)

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Benefit (\$)	Outlet (\$)	Total (\$)	Equivalent Ha.
<u>4. Privately-Owned Non-Agricultural Lands</u>								
3	Pt Lot 1	0.4	19	R. & M. Ferriss	-	189	189	0.8
	Pt Lot 2	0.3	25	J. & A. Brush	-	5	5	0.6
	Pt Lot 3	2.9	30	K. Pritchard & L. Roessler-Pritchard	213	-	213	2.9
	Pt Lot 3	0.7	29	M. Heleeji	-	5	5	1.4
	Pt Lot 3	0.2	28	R. & C. Shaw	-	1	1	0.4
	Pt Lot 3	0.4	27	F. Randall & J. Cooke	-	3	3	0.9
<u>5. Privately-Owned Agricultural Lands (Eligible for Available Grants)</u>								
3	Pt Lot 1	13.8	20	Miller Cattle and Grain Ltd.	1,567	998	2,565	13.8
	Pt Lot 1	12.2	21	S. Zavaros	163	664	827	12.2
	Pt Lot 2	19.7	22	B. & N. Gorski	469	500	969	19.7
	Pt Lot 2	38.3	24	J. & A. Brush	475	307	782	38.3
	Pt Lot 2	6.1	23	L. McLean	-	49	49	6.1
	Pt Lot 3	18.5	26	J. Grondin	238	63	301	18.5
					<u>6,465</u>	<u>3,079</u>	<u>9,544</u>	
Total - Benefit					6,465			
Total - Outlet					<u>3,079</u>			
Total - Town of Essex					9,544			
Total - Town of Amherstburg					306			
Total - Town of Essex					<u>9,544</u>			
Total Assessment					\$ 9,850			

Charles Shepley Branch Drain  
 Town of Amherstburg  
 January 18, 2021

**SCHEDULE OF MAINTENANCE - CHARLES SHEPLEY BRANCH DRAIN  
 SECTION 1 - STATION 4+000 TO STATION 4+990**

For maintaining the section of the Charles Shepley Branch Drain between 4+000 (Outlet to the Charles Shepley Drain ) and Station 4+990. The culverts are to be maintained in accordance with the culvert maintenance table in the maintenance section of the Report.

Conc.	Lot or Part	Affected Hect.	Owner I.D. Number	Owner	Benefit (\$)	Outlet (\$)	Total (\$)
<b><u>Town of Amherstburg</u></b>							
<b><u>5. Privately-Owned Agricultural Lands (Eligible for Available Grants)</u></b>							
9	Pt Lot 102	19.4	7	Grondin Farms Ltd	765	1,414	2,179
	Pt Lot 102	12.0	8	Bonnefield Farmland Ontario	1,710	-	1,710
	Pt Lot 103	4.1	10	Grondin Farms Ltd	-	1,061	1,061
					<u>2,475</u>	<u>2,475</u>	<u>4,950</u>
				Total - Benefit	2,475		
				Total - Outlet	2,475		
				Total Assessment	<u>\$ 4,950</u>		

Charles Shepley Main Drain and  
Charles Shepley Branch Drain  
Town of Amherstburg  
January 18, 2021

## SPECIFICATION OF WORK

### **1. Scope of Work**

The work to be included in this specification includes the removal and replacement access culverts and drain maintenances.

### **2. General**

Each tenderer must inspect the site prior to submitting their tender and satisfy themselves by personal examination as to the local conditions that may be encountered during this project. The Contractor shall make allowance in the tender for any difficulties which they may encounter. Quantities or any information supplied by the Engineer is not guaranteed and is for reference only.

All work and materials shall be to the satisfaction of the Drainage Superintendent who may vary these specifications as to minor details but in no way decrease the proposed capacity of the drain.

The Contractor shall be responsible for the notification of all utilities prior to the start of construction.

### **3. Plans and Specifications**

These specifications shall apply and be part of the contract along with the General Specifications for Open Drains. This specification of work shall take precedence over all plans and general conditions pertaining to the contract. The Contractor shall provide all labour, equipment, and supervision necessary to complete the work as shown in the plans and described in these specifications. Any work not described in these specifications shall be completed according to the applicable Ontario Provincial Standard Specifications and Standard Drawings.

#### **4. Health and Safety**

The Contractor at all times shall be responsible for health and safety on the worksite including ensuring that all employees wear suitable personal protective equipment including safety boots and hard hats.

The Contractor shall be responsible for traffic control as per the Ontario Traffic Manual Book 7 – Temporary Conditions (latest revision) when working on public road allowances. A copy of a traffic control plan shall be kept on site at all times. The Contractor shall maintain suitable barricades, warning lights, and temporary traffic notices, at his expense, in their proper position to protect the public both day and night. Flagmen are the responsibility of the Contractor when working on the road allowance and when entering or exiting a worksite onto a roadway.

The Contractor shall be responsible to ensure that all procedures are followed under the Occupational Health and Safety Act to ensure that work sites are safe and that accidents are prevented. In the event of a serious or recurring problem, a notice of noncompliance will be issued. The Contractor will be responsible for reacting immediately to any deficiency and correcting any potential health and safety risk. Continuous disregard for any requirement of the Occupational Health and Safety Act could be cause for the issuance of a stop work order or even termination of the contract.

He shall also ensure that only competent workmen are employed onsite and that appropriate training and certification is supplied to all employees.

#### **5. Workplace Safety and Insurance Board**

Upon award of the contract and prior to commencement of work, the Contractor shall furnish the Town of Amherstburg with a satisfactory Certificate of Insurance (COI) containing the information below, for the period of the execution of the work:

- i. A Commercial General Liability (CGL) policy that shall be not less than 5 million dollars per occurrence.
- ii. The CGL policy shall include bodily injury including death, personal injury, property damage, tenants legal liability, non-owned automobile and contain a cross liability/severability of interest clause. The certificate must also include acknowledgement that coverage under the policy specifically extends to the works in question. The COI shall name the Town of Amherstburg as additional insured to the policy.

- iii. The CGL policy shall not contain any exclusion or limitation in respect to shoring, underpinning, raising or demolition of any building or structure, pile driving, caisson work, collapse of any structure or subsidence of any property, structure or land from any cause.
- iv. The Contractor shall note that where construction works are performed within lands owned by the County of Essex or Ministry of Transportation the CGL policy shall also name the County of Essex and/or the Ministry of Transportation as additional insured to the policy.
- v. The liability insurance shall be endorsed to provide that the policy shall not be altered, cancelled or allowed to lapse without 30 days prior written notice to the Town of Amherstburg.

#### **6. MNRF Drain Registration**

The Contractor is advised that the Town of Amherstburg has conducted an "Endangered Species Act Review" and has registered its drainage activities with the Ministry of Natural Resources and Forestry.

The Town of Amherstburg, in pursuant to the Endangered Species Act Municipal Agreement, has identified the potential presence of certain species within the project area. It is the responsibility of the Contractor to make certain that necessary provisions are undertaken to ensure the protection of all species at risk and their habitats throughout the course of construction. It is also the responsibility of the Contractor to make itself familiar with the following documents:

1. Town of Amherstburg – Complete Mitigation Documents
2. Town of Amherstburg - Additional Mitigation Measures for Snakes Species
3. Town of Amherstburg - Additional Mitigation Measures for Turtle Species
4. Snakes of Ontario Identifier Guide
5. Turtles of Ontario Identifier Guide

These documents will be provided to the successful bidder.

The Contractor will be responsible for providing the necessary equipment and materials required by the mitigation plans and shall contact the Town of Amherstburg Drainage

Superintendent immediately if any endangered species are encountered during construction.

### **7. Benchmarks**

The benchmarks are based on geodetic elevations. The benchmark information is available on the plan and profile drawings.

### **8. Access and Working Area**

Access to the work site shall be gained from road allowances when possible, along existing private lanes and along the fence lines. Access to the drainage works shall be supplied through each property. Access to the working area along the private lanes and fence lines shall be restricted to a width of 6 m.

The working area shall be on the same side of the drain on which the excavated material is disposed of. The working corridor is 10.0 m. The working corridor will be measured from the adjacent finished top of bank.

Access for culvert installation or replacements shall be from the property which the culvert is located in. The access shall be along the property line or as agreed to by the landowner. When possible, maintenance should be completed when crops are off.

The working area around culverts shall extend to 12m from the adjacent finished top of bank on each side of the drain for a distance of 20.0 m upstream and downstream of the culvert.

The excavated earth from Station 0+000 to Station 1+813 shall be cast onto the adjacent lands to the west. From Station 1+813 to 3+786 the excavated material shall be cast onto the adjacent lands to the east and south. When a drain passes in front of any house, lawn, garden driveway orchard etc. the excavated material shall be hauled away and spread upon the adjoining lands or as directed by the Drainage Superintendent. The Contractor will be required to haul material more than 150m.

The excavated earth from Station 4+000 to Station 4+684 shall be cast onto the adjacent lands to the south. From Station 4+684 to 4+983 the excavated material shall be cast onto the adjacent lands to the east.

**9. Removal of Existing Access Culverts**

The existing access culverts shall be removed in their entirety from the open channel. The steel culvert, concrete rubble and excavated material shall be disposed offsite at the expense of the Contractor.

When mailboxes or 911 signs need to be removed to facilitate construction, the Contractor shall remove, store and reinstall them for the duration of the culvert installation. The mailbox or sign shall be reinstalled to the existing conditions or better using the existing materials.

Removals in accordance with OPSS 511.

**10. Brushing and Tree Removal**

All brush, trees, woody vegetation, etc. shall be removed from the working area/allowance of the drain. Trees and brush shall be removed in their entirety including stumps and piled and burnt by the Contractor. Trees and brush on the side slopes shall be close cut.

Brush can be cut with a chainsaw. A mechanical tree shear mower can be used on brush smaller than 35 mm in diameter. The Contractor shall be responsible for obtaining all necessary burning permits.

Certain trees may be left in place at the direction of the Drainage Superintendent. Any trees to be salvaged by the individual landowners shall be removed by the landowners with all resulting brush and branches cleaned up prior to the start of construction. If the Contractor agrees to remove any trees and set them aside for a landowner, the landowner will be responsible for any cleanup as above.

Brushing and tree removal in accordance with OPSS 201.



**11. Excavation of Channel**

Channel works shall have a minimum of 1.5H:1V side slopes.

The side slopes of any disturbed areas shall be seeded as soon as the final grading is completed. The channel shall be excavated to the proper depth using a laser or similar approved device with a labourer onsite to ensure correctness of grade and to confirm location of tile ends.

Spoils shall be placed a minimum 1.5 m back from the top of the bank. The excavated material shall be placed and levelled to a maximum depth of 200 mm and shall not impede overland drainage or cultivation of the land using farm machinery. If the spoils have sub-soil in them, the topsoil shall be windrowed along the edge of the working corridor prior to placing the sub-soil. After the excavated material has been levelled, the topsoil shall be spread to its original depth and left in a condition suitable for cultivation.

If landowners request the spoils be disposed of outside the working area, a sign-off from the receiving property must be obtained. Costs associated with disposing of spoils outside the working area are the responsibility of the Contactor. No additional payment will be made for disposing of spoils outside the working area.

Excavation in accordance with OPSS 206.

Restoration shall be in accordance with the restoration specification.

**12. Installation of Culvert**

The Contractor shall supply, install, and backfill pipe culverts. High density polyethylene (HDPE) smooth wall pipe (320 kPa) for pipe culvert sizes 900 mm and smaller shall be Boss 2000 or approved equal with coupler joints. Corrugated Steel Pipe (CSP) culverts shall be aluminized CSP with a minimum wall thickness of 2.8 mm in all cases. All corrugation profiles shall be of helical lockseam manufacture using 68 mm x 13 mm corrugations for 1600 mm diameter pipe and smaller and 125 mm x 25 mm corrugations for 1800 mm diameter pipe and larger. Pipe with 125 mm x 25 mm corrugations shall be used if 68 mm x 13 mm corrugations are not available. Future culvert replacements shall be to the same specifications

The proposed access culvert shall be installed in the same general location as the existing culvert with the exception of Culvert 1 which will be relocated to the south property limit. The culvert shall be installed with the invert 10% (minimum 150 mm) below the proposed channel bottom elevation, as shown on the drawings. The location

of the culvert may be moved a short distance upstream or downstream if approved by the Drainage Superintendent or Engineer.

If a landowner requests a longer culvert than that specified above, please refer to the report.

The culvert length is based on using rip rap ends. If concrete block ends are to be utilized in the future, the culvert will be shortened the travelled portion plus the width of the concrete block headwalls. The culvert may be moved upstream or downstream as necessary to avoid existing tile outlets. If the pipes cannot be avoided, they shall be extended upstream or downstream of the proposed culvert and shall be done with non-perforated HDPE agricultural tubing with a manufactured coupling, elbow and rodent grate. Any tile outlets extended as a result of extra length requested by a landowner shall be extended at the landowner's expense.

The bottom of the excavation shall be excavated to the required depth with any over excavation backfilled with granular material or drainage stone. When the pipe has been installed to the proper grade and depth, the excavation shall be backfilled with granular or drainage stone from the bottom of the excavation to the springline of the pipe. Care shall be taken to ensure that the backfill on either side of the culvert does not differ by more than 300 mm so that the pipe is not displaced.

Access culverts shall be backfilled from the springline to finished grade with free draining native material or Granular "B" to within 300 mm of finished grade. The top 300 mm shall be backfilled with compacted Granular "A" material to finished grade. If excavated material is found unsuitable for backfill purposes, then Granular 'B' material will be required as backfill at the expense of the drainage works.

Municipal road culverts shall be backfilled from the springline to finished grade with Granular "B" to within 500 mm of finished grade. The top 500 mm shall match the existing road base materials.

All granular bedding and backfill material shall be mechanically compacted to 95% standard proctor maximum dry density. The Granular "B" material shall be mechanically compacted to 98% standard proctor maximum dry density and the Granular "A" material shall be mechanically compacted to 100% standard proctor maximum dry density.

Rip rap ends are to be used with 1.5H:1V side slopes. The rip rap shall consist of 100 mm x 250 mm quarry stone or approved equal. The area to receive the rip rap shall be graded to a depth of 400 mm below finished grade. Filter fabric (Terrafix 270R or approved equal) shall then be placed with any joints overlapped a minimum 600mm. The quarry stone shall then be placed with the smaller pieces placed in the gaps and voids to give it a uniform appearance.

If concrete blocks are used the concrete blocks shall have dimensions of approx. 600 mm x 600 mm x 1200 mm, 600 mm x 600 mm x 2400 mm or 300 mm x 600 mm x 1200 mm as required. The top of the culvert shall govern block elevation. The correct block shall be set with the top of the block equal to the top of the culvert. The blocks shall be set at each end of the culvert so that each row of blocks will be offset approx. 100mm from the row below. The bottom row shall consist of one block placed parallel to the culvert. The blocks shall be imbedded a minimum of 300 mm into each bank and shall extend into the drain bottom to match the pipe invert or below.

The blocks shall be placed over a layer of filter fabric (Terrafix 270R or approved equal). The culvert shall be backfilled in conjunction with the placement of the blocks. The gaps between the culvert and the blocks shall be filled with concrete cinder blocks/bricks and mortar to give the endwall a finished appearance.

Excavation in accordance with OPSS 206.

Compaction in accordance with OPSS 501.

Granular in accordance with OPSS 1010.

### **13. Access at Station 3+786 (Access 8)**

The Contractor will be required to remove any topsoil within the footprint of the access and stockpile it for restoration. Any existing tiles or culverts encountered during Construction shall be extended to the open channel at an expense to the drain. The drain shall be backfilled with imported fill to within 300 mm of finished grade. The top 300 mm shall be backfilled with compacted granular "A" material to finished grade.

All imported fill shall be mechanically compacted to 95% standard proctor maximum dry density. The Granular "A" material shall be mechanically compacted to 100% standard proctor maximum dry density.

Compaction in accordance with OPSS 501.

Granular in accordance with OPSS 1010.

#### **14. Subsurface Drainage**

All existing subsurface drains encountered during construction shall be reconnected to the open channel unless otherwise noted on the drawings or as directed by the Drainage Superintendent. The downstream end shall be plugged to the satisfaction of the Drainage Superintendent.

#### **15. Trucking of Excavated Material**

When a drain passes in front of any house, lawn, garden driveway orchard etc. the excavated material shall be loaded, hauled away and spread upon the adjoining lands or as directed by the Drainage Superintendent. The Contractor will to be required to haul material more than 150 m. The cost of trucking will form part of the drain maintenance cost and be assessed as per the Schedule of Maintenance.

If other agricultural landowners request the spoils be disposed of outside the working area, a sign-off from the receiving property must be obtained. Costs associated with disposing of spoils outside the working area are the responsibility of the Contractor. No additional payment will be made for disposing of spoils outside the working area.

#### **16. Silt Fence**

Light duty silt fencing shall be installed immediately downstream of any channel works or culvert replacements for the duration of construction. The silt fence shall consist of filter fabric or manufactured silt fence supported with posts.

The light duty silt fencing shall be supplied and installed in accordance with OPSS 577 and OPSD 219.110. The light duty silt fencing shall be removed once the disturbed area has been revegetated.

#### **17. Restoration**

Road restoration shall be in accordance with the following:

Disturbed areas within the road right-of-way shall be restored in accordance with 100 mm of native topsoil and seed. Topsoil in accordance with OPSS 802. Seed in accordance with OPSS 804.

Seeding Application rates are as follows:

- Primary seed (85 kg/ha.) consisting of 50% red fescue, 40% perennial ryegrass and 5% white clover.
- Nurse crop consisting of Italian (annual) ryegrass at 25% of total weight.

- Fertilizer (300 kg/ha.) consisting of 8-32-16.

### **18. Environmental Considerations**

The Contractor shall take care to adhere to the following considerations.

1. All excavated and stockpiled material shall be placed a minimum of 1.5 m from the top of the bank. Material shall not be placed in surface water runs or open inlets that enter the channel.
2. All granular and erosion control materials shall be stockpiled a minimum of 1.5 m from the top of the bank. Material shall not be placed in surface water runs or open inlets that enter the channel.
3. All activities, including maintenance procedures, shall be controlled to prevent the entry of petroleum products, debris, rubble, concrete, or other deleterious substances into the water. Vehicle and equipment refuelling and maintenance shall be conducted away from the channel, any surface water runs, or open inlets. All waste materials shall be stockpiled well back from the top of the bank and all surface water runs and open inlets that enter the drain.
4. All construction in the channel shall be carried out during periods of low flow. The Contractor shall maintain a dry working area during construction. A temporary dam consisting of excavated material shall be constructed upstream and downstream of the work area if working during low water flow. The temporary dams shall be covered with filter fabric or plastic that shall be anchored with rip rap material or broken concrete. Water shall be bailed and pumped from the work area to an area downstream of the temporary dam and upstream of the silt fence. Water will be controlled in the area between the two temporary dams for the duration of construction using pumps, if necessary.

After completion of the construction, the temporary dams and any collected sediment shall be removed. The final removal shall be the silt fence. By following the above procedure, the work should have little or no impact on the existing channel if carried out during low flows.

5. The Contractor shall take care to adhere to the following Best Management Practices prepared by the Department of Fisheries and Ocean.
  - a) Culvert Replacements in Municipal Drains (Appendix A)

6. The Contractor shall take care to familiarize them with the Town of Amherstburg's mitigation documents and species identification guidelines which will be provided to the successful bidder.

**19. Culvert Maintenance**

The Contractor shall be responsible for maintenance of the access culverts for a period of one year after their installation. This will include repairing any settlement areas on the travel surface with Granular "A".

**20. Miscellaneous**

Any subsurface drains encountered upstream of the culvert that conflict with the proposed culvert shall be extended to an outlet to the open channel to the approval of the Drainage Superintendent.

Any fences that must be removed to allow construction or maintenance shall be reinstalled by the Contractor using the existing materials.

The contractor may be required to work around utilities.

It is the landowner's responsibility to mark all tile and tile mains prior to maintenance being carried out.

# APPENDIX A



Fisheries and Oceans  
Canada

Pêches et Océans  
Canada

Ontario and Prairie Region  
Fish and Fish Habitat Protection Program  
867 Lakeshore Rd.  
Burlington, ON  
L7S 1A1

Région de l'Ontario et des Prairies  
Programme de protection du poisson et de son habitat  
867 chemin Lakeshore  
Burlington, ON  
L7S 1A1

December 21, 2020

*Our file*      *Notre référence*  
**20-HCAA-02438**

Michael Gerrits  
4218 Oil Heritage Road, P.O. Box 1928  
Petrolia, ON N0N 1R0

**Subject: Culvert Replacements, Charles Shepley Drain, Town of Amherstburg (20-HCAA-02438) – Implementation of Measures to Avoid and Mitigate the Potential for Prohibited Effects to Fish and Fish Habitat**

Dear Michael Gerrits:

The Fish and Fish Habitat Protection Program (the Program) of Fisheries and Oceans Canada (DFO) received your proposal on November 27, 2020. We understand that you propose to:

- Remove existing 2m x 7m CSP culvert and install new 2.2m x 10.5m CSP culvert in a new location;
- Replace existing 1.2m x 8m CSP culvert with new 1.6m x 12m CSP culvert;
- Remove existing 900mm x 2m CSP culvert and infill approximately 9m of channel at the top end of the drain with riprap;
- Perform all activities in adherence to the [Best Management Practices- Culvert Replacements in Municipal Drains](#); and
- Restore any disturbed areas following work completion.

Our review considered the following information:

- Request for Review form and associated documents submitted on November 27, 2020.

Your proposal has been reviewed to determine whether it is likely to result in:

- the death of fish by means other than fishing and the harmful alteration, disruption or destruction of fish habitat which are prohibited under subsections 34.4(1) and 35(1) of the *Fisheries Act*; and
- effects to listed aquatic species at risk, any part of their critical habitat or the residences of their individuals in a manner which is prohibited under sections 32, 33 and subsection 58(1) of the *Species at Risk Act*.



The aforementioned impacts are prohibited unless authorized under their respective legislation and regulations.

To avoid and mitigate the potential for prohibited effects to fish and fish habitat (as listed above), we recommend implementing the measures listed below:

- Plan in-water works, undertakings and activities to respect timing windows to protect fish, including their eggs, juveniles, spawning adults and/or the organisms upon which they feed and migrate;
- Capture, relocate and monitor for fish trapped within isolated, enclosed, or dewatered areas;
- Conduct in-water undertakings and activities during periods of low water levels;
- Limit the duration of in-water works, undertakings and activities so that it does not diminish the ability of fish to carry out one or more of their life processes (spawning, rearing, feeding, migrating);
- Limit impacts on riparian vegetation to those approved for the work, undertaking or activity;
- Replace/restore any other disturbed habitat features and remediate any areas impacted by the work, undertaking or activity;
- Develop and implement an erosion and sediment control plan to avoid the introduction of sediment into any waterbody during all phases of the work, undertaking or activity;
  - Install effective erosion and sediment control measures prior to beginning work, undertaking or activity in order to stabilize all erodible and exposed areas;
  - Monitor the watercourse to observe signs of sedimentation during all phases of the work, undertaking or activity and take corrective action;
  - Schedule work to avoid wet, windy and rainy periods (and heed weather advisories) that may result in high flow volumes and/ or increase erosion and sedimentation;
  - Operate machinery on land in stable dry areas; and,
- Develop and implement a response plan to avoid a spill of deleterious substances

Provided that you incorporate these measures into your plans, the Program is of the view that your proposal will not require an authorization under the *Fisheries Act*, the *Aquatic Invasive Species Regulations* or the *Species at Risk Act*.

Should your plans change or if you have omitted some information in your proposal, further review by the Program may be required. Consult our website (<http://www.dfo-mpo.gc.ca/pnw-ppe/index-eng.html>) or consult with a qualified environmental consultant to determine if further review may be necessary. It remains your responsibility to remain in compliance with the *Fisheries Act* and the *Species at Risk Act*.

It is also your *Duty to Notify* DFO if you have caused, or are about to cause, the death of fish by means other than fishing and/or the harmful alteration, disruption or destruction of

fish habitat. Such notifications should be directed to (<http://www.dfo-mpo.gc.ca/pnw-ppe/CONTACT-eng.html>).

We recommend that you notify this office at least 10 days before starting your project and that a copy of this letter be kept on site while the work is in progress. It remains your responsibility to meet all other federal, territorial, provincial and municipal requirements that apply to your proposal.

If you have any questions with the content of this letter, please contact Kyle Mataya at [Kyle.Mataya@dfo-mpo.gc.ca](mailto:Kyle.Mataya@dfo-mpo.gc.ca). Please refer to the file number referenced above when corresponding with the Program.

Yours sincerely,

A handwritten signature in black ink, appearing to read 'K. Mataya', written in a cursive style.

Kyle Mataya  
Biologist, Triage and Planning  
Fish and Fish Habitat Protection Program

**mike@mgerritsconsulting.ca**

---

**From:** Ashley Gyori <AGyori@erca.org>  
**Sent:** Wednesday, November 25, 2020 2:43 PM  
**To:** mike@mgerritsconsulting.ca  
**Subject:** RE: 2019-1021 Charles Shepley Drain Draft Plans (November 2, 2020), 2019-1021 Charles Shepley Drain Draft Report (November 2, 2020)  
**Attachments:** ERCA Watershed Management Services 2020 Fee Schedule.pdf

Good afternoon,

We acknowledge receipt of the Draft Engineering Report and Plans for the proposed drainage works to the Charles Shepley Drain. We have reviewed the plans prepared by your office, Project No. 2019-1021, and have determined that the draft proposal satisfies this office's concerns with respect to Section 28 of the *Conservation Authorities Act*.

For this project to proceed, we will need a copy of the signed and sealed final drainage report and drawings and an ERCA application for permit form, completed by the municipality. Our office will invoice the Town of Amherstburg the application for permit fee of \$800.00 in accordance with Item 22 of the attached Board-approved Fee Schedule, upon issuance of the approval.

If you have any questions, please do not hesitate to contact me.

Kind regards,



**ASHLEY GYORI**  
Regulations Analyst  
Essex Region Conservation Authority  
360 Fairview Avenue West, Suite 311 • Essex, Ontario • N8M 1Y6  
P. 519-776-5209 x 247 • F. 519-776-8688  
[agyori@erca.org](mailto:agyori@erca.org) • [essexregionconservation.ca](http://essexregionconservation.ca)

**Please consider the environment before printing this email**

*This e-mail transmission is confidential and may contain proprietary information for the express use of the intended recipient. Any use, distribution or copying of this transmission, other than by the intended recipient, is strictly prohibited. If you are not the intended recipient, please notify us by telephone at the number above and arrange to return this transmission to us or destroy it.*

**Follow us on Twitter: @essexregionca**

**\*\* Please note that the ERCA office is closed to the public; however, staff are continuing to respond to inquiries and review applications in a modified capacity. We appreciate your understanding and patience at this time.\*\***

-----Original Message-----

**From:** Dan Jenner <DJenner@erca.org>  
**Sent:** Monday, November 9, 2020 7:30 AM  
**To:** Ashley Gyori <AGyori@erca.org>  
**Subject:** FW: 2019-1021 Charles Shepley Drain Draft Plans (November 2, 2020), 2019-1021 Charles Shepley Drain Draft Report (November 2, 2020)

DAN JENNER

Regulations Coordinator  
Essex Region Conservation Authority  
360 Fairview Avenue West, Suite 311 Essex, Ontario N8M 1Y6  
P. 519-776-5209 x 359 F. 519-776-8688

djenner@erca.org essexregionconservation.ca Please consider the environment before printing this email This e-mail transmission is confidential and may contain proprietary information for the express use of the intended recipient. Any use, distribution or copying of this transmission, other than by the intended recipient, is strictly prohibited. If you are not the intended recipient, please notify us by telephone at the number above and arrange to return this transmission to us or destroy it. Follow us on Twitter: @essexregionca

\*\*NOTE: As per public health guidelines, our offices are closed to the public, but staff are working remotely to provide responses to inquiries and review applications as efficiently as possible. Your patience and understanding is greatly appreciated at this time. \*\*

-----Original Message-----

From: mike@mgerritsconsulting.ca <mike@mgerritsconsulting.ca>  
Sent: Tuesday, November 3, 2020 9:16 AM  
To: Dan Jenner <DJenner@erca.org>  
Subject: 2019-1021 Charles Shepley Drain Draft Pans (November 2, 2020), 2019-1021 Charles Shepley Drain Draft Report (November 2, 2020)

Hello Dan,

Please review the report and forward any comments. We had some original comments from ERCA. If you would like I can send them to you. They said we had to consider ice damming and the 100 year flood levels. The culverts are equal or larger than the existing conditions. Please review the replacement spec for Culvert 2, it is a concrete box culvert however the culverts upstream and downstream are smaller csp's. In the future is it possible to replace the box culvert with a smaller CSP that matches the adjacent culverts.

Thanks

Mike



## Best Management Practices – Culvert Replacements in Municipal Drains

This document describes the conditions on which one may proceed with a culvert replacement in a municipal drain without DFO approval/notification. All municipal, provincial, or federal legislation that applies to the work being proposed must be respected. If the conditions/requirements below cannot be met, please complete the drain notification form and submit it to the Fisheries Protection Program form review at: [FisheriesProtection@dfo-mpo.gc.ca](mailto:FisheriesProtection@dfo-mpo.gc.ca).

### Potential Impacts to Fish Habitat

- Infilling fish habitat by encroachment of the water crossing footprint or channel realignment to accommodate culvert
- Harmful substrate alteration of fish habitat (e.g. blockage of groundwater upwellings, critical SAR habitat, spawning areas)
- Removal of riparian vegetation and cover along the banks of the municipal drain
- Removal of edge habitat (e.g. undercut bank, shallower areas with lower velocity, aquatic vegetation) creation of barriers to fish movement (e.g. perched crossings, velocity barriers, alteration of the natural stream gradient)
- Alteration of channel flow velocity and/or depth (e.g. oversized culvert resulting in insufficient depth for fish passage at low flow or undersized culvert resulting in a flow velocity barrier at high flow)
- Alteration of channel morphology and sediment transport processes caused by the physical structure of the crossing resulting in upstream and downstream sediment aggradation/erosion
- Re-entry of sediment that was removed/stockpiled into the watercourse
- Erosion downstream from sudden release of water due to the failure of site isolation
- Stranding of fish in isolated ponds following de-watering of the site
- Impingement or entrainment of fish when de-watering pumps are used
- Short term or chronic transport of deleterious substances, including sediment, into fish habitat from construction or road drainage

### Requirements

The following requirements must be met:

- There are no aquatic Species at Risk present in the work zone or impact zone. To confirm there are no aquatic Species at Risk present, refer to the document, [A Guide for Interpreting Fish and Mussel Species at Risk Maps in Ontario](#) which can be found at: <http://www.dfo-mpo.gc.ca/Library/356763.pdf>. Links for Ontario Conservation Area specific fish and mussel maps that include critical habitat extents and a list of aquatic Species at Risk found within the conversation authority boundary can be found on Page 5 of [A Guide for Interpreting Fish and Mussel Species at Risk Maps in Ontario](#).
- The culvert is embedded into the streambed and must allow for the free passage of fish.
- The work involves like-for-like replacements of existing road or private access culverts on all drain types without SAR.
- On C and F Drains only, this can also include replacements with extensions and end walls for the purposes of providing the property or road with safe access, but the project permanent footprint will not increase more than 250 m<sup>2</sup> below the high water mark.
- The project does not involve replacing a bridge or arch with one or more culverts installed in parallel or a larger-diameter culvert with more than one culvert installed in parallel.

- The project does not involve building more than one culvert installed in parallel on a single watercourse crossing site (e.g. twin culvert).
- The project does not involve temporarily narrowing the watercourse to an extent or for a duration that is likely to cause erosion, structural instability or fish passage problems.
- The municipal drain has no flow/low flow or is frozen to the bottom at the time of the replacement.
- In-water work is scheduled to respect timing windows (Tables 1 and 2) to protect fish, including their eggs, juveniles, spawning adults, and/or the organisms upon which they feed.
- The work can be conducted using the Culvert Removal Method described below and Standard Measures to Avoid Causing *Serious Harm to Fish* will be implemented when required.

Note: If your project must be conducted without delay in response to an emergency (e.g. the project is required to address an emergency that poses a risk to public health or safety or to the environment or property), you may apply for an Emergency Authorization (<http://www.dfo-mpo.gc.ca/asp/forceDownload.asp?FilePath=/pnw-ppe/reviews-revues/Emergency-Authorizations-Autorisations-Urgences-eng.pdf>).

### **Culvert Removal Methodology**

- Plan/manage the work site in a manner that prevents sediment from entering the municipal drain by installing sediment and erosion control materials where required. Ensure that a sediment and erosion control plan is developed and modified as necessary for the site.
- Where required, install effective erosion and sediment control measures before starting work to prevent sediment from entering the municipal drain.
- Implement site isolation measures when in-water work is required.
  - Install an impervious barrier upstream of the work area (Figure 1). If possible, install a secondary barrier upstream of the work area for added protection.
  - Attempt to drive out the fish from the work area and then install the impervious barrier downstream of the work area. This may reduce or eliminate the need for a fish salvage.
  - When the drain is flowing, maintain downstream flows (e.g. bypass water around the work site using pumps or flume pipes; Figure 2). Provide temporary energy dissipation measures (e.g. rip-rap) at discharge point of the hose or temporary outlet pipe when required. Routinely inspect bypass pump and hose or pipe to ensure proper operation. Inspect discharge point for erosion and reposition hose/pipe or install additional temporary energy dissipation material as needed.
  - Dewater the isolated work area. The hose for a pump may discharge along the top of the bank into existing vegetation; however, the area should be monitored for signs of erosion. Reposition the hose or install additional temporary energy dissipation material as needed.
  - A fish screen with openings no larger than 2.54 mm (0.10 inches) should be equipped on any pump used during the operation. Note: Additional information regarding fish screens can be found in the DFO Freshwater Intake End-of-Pipe Fish Screen Guideline document (<http://www.dfo-mpo.gc.ca/Library/223669.pdf>).
  - Collect any fish present in the isolated work area and relocate them downstream.
  - Fish salvage operations must be conducted under a license issued by the Ontario Ministry of Natural Resources and Forestry (MNRF). The MNRF should be contacted well in advance of any work to obtain the required fish collection license.
- Install the culvert so that it is embedded into the streambed; ensure the culvert remains passable (e.g. does not become perched) by fish and wildlife.



- Decommission the site isolation in a manner that minimizes the introduction of sediment. The downstream isolation barrier shall gradually be removed first, to equalize water levels inside and outside of the isolated area and to allow suspended sediments to settle.
- Stabilize and remove waste from the site.
- Where required, maintain effective erosion and sediment control measures until complete re-vegetation of disturbed areas is achieved.



Figure 2. Isolation of Site




Figure 3. Isolation and Bypass Diversion when Working In-Water



## Timing Windows

Figure 1 and Tables 1 and 2 can be used to determine the Restricted Activity period for the drain based on its classification. Note: Timing windows identified on [Conservation Authority](#) permits or [Ministry of Natural Resources](#) (Government of Ontario) work permits may differ and take precedence.



**Figure 1. Ontario's Northern and Southern Region boundaries for determining application of restricted activity timing windows.**

**Table 1. Restricted Activity timing windows for the protection of spawning fish and developing eggs and fry in the Northern Region. Dates represent when work should be avoided.**

DRAIN TYPE	RESTRICTED ACTIVITY PERIOD
A	SEPTEMBER 1 TO JULY 15
B	SEPTEMBER 1 TO JULY 15
C	APRIL 1 TO JULY 15
D	SEPTEMBER 1 TO JULY 15
E	APRIL 1 TO JULY 15

**Table 2. Restricted Activity timing windows for the protection of spawning fish and developing eggs and fry in the Southern Region. Dates represent when work should be avoided.**


DRAIN TYPE	RESTRICTED ACTIVITY PERIOD
A	SEPTEMBER 15 TO JULY 15
B	MARCH 15 TO JULY 15
C	MARCH 15 TO JULY 15
D	OCTOBER 1 TO JULY 15
E	MARCH 15 TO JULY 15

### Standard Measures to Avoid Causing *Serious Harm to Fish*

When implementing a culvert removal project in a municipal drain, the *Fisheries Act* still requires an individual/company to ensure they avoid causing *serious harm to fish* during any activities in or near water. The following advice will help one avoid causing harm and comply with the *Act* (for additional information see <http://www.dfo-mpo.gc.ca/pnw-ppc/measures-mesures/measures-mesures-eng.html>).

1. Schedule work to avoid wet, windy and rainy periods that may increase erosion and sedimentation.
2. Whenever possible, operate machinery on land above the high water mark or on ice and in a manner that minimizes disturbance to the banks and bed of the municipal drain.
  - Ensure that machinery arrives on site in a clean condition and is maintained free of fluid leaks.
  - Limit machinery fording of the municipal drain to a one-time event (i.e., over and back), and only if no alternative crossing method is available. If repeated crossings of the municipal drain are required, construct a temporary crossing structure.
  - Wash, refuel and service machinery and store fuel and other materials for the machinery in such a way as to prevent any deleterious substances from entering the water.
  - Keep an emergency spill kit on site in case of fluid leaks or spills from machinery.
3. Install effective sediment and erosion control measures before starting work to prevent sediment from entering the municipal drain. Inspect them regularly during the course of construction and make all necessary repairs if any damage occurs.
4. Erosion and sediment control measures should be maintained until all disturbed ground has been permanently stabilized, suspended sediment has resettled to the bed of the municipal drain and runoff water is clear.
5. Undertake all in-water activities in isolation of open or flowing water while maintaining the natural flow of water downstream and avoid introducing sediment into the municipal drain.
6. Ensure applicable permits for relocating fish are obtained and relocate any fish that become trapped in isolated pools or stranded in newly flooded areas to the main channel of the watercourse.
7. Ensure that the water that is being pumped/diverted from the site is filtered (sediment remove) prior to being released (e.g. pumping/diversion of water to a vegetated area).
8. Implement measures for containing and stabilizing waste material (e.g. dredging spoils, construction waste and materials, commercial logging waste, uprooted or cut aquatic plants, accumulated debris) above the high water mark of nearby waterbodies to prevent re-entry.
9. Stabilize shoreline or banks disturbed by any activity associated with the project to prevent erosion and/or sedimentation, preferably through re-vegetation with native species suitable for the site.
10. If replacement rock reinforcement/armouring is required to stabilize eroding or exposed areas, then ensure that appropriately-sized, clean rock is used; and that rock is installed at a similar slope to maintain a uniform bank/shoreline and natural stream/shoreline alignment.
11. Remove all construction materials from site upon project completion.





**OWNER INDEX**

3.	M. & A. BEETHAM	1.0 Ha
9.	S. & K. KLOMP	0.41 Ha
19.	R. & M. FERRISS	0.41 Ha
25.	J. & A. BRUSH	0.29 Ha
34.	A. LISER & M. SAHINDIS	0.43 Ha
33.	L. PILLON	0.17 Ha
32.	K. KIMBALL	1.56 Ha
35.	K. KIMBALL	0.76 Ha
29.	M. HELEEJI	0.69 Ha
28.	R. & C. SHAW	0.20 Ha
27.	F. RANDALL & J. COOKE	0.44 Ha
17.	S. SCURK	0.38 Ha




**LEGEND**

	EXISTING CULVERT		LANDOWNER IDENTIFICATION NUMBER
	CULVERT TO BE REMOVED		CHARLES SHEPLEY MAIN DRAIN AND BRANCH DRAIN
	CULVERT TO BE REPLACED		MUNICIPAL DRAIN
	DRAINAGE AREA		



4218 Oil Heritage Road  
Patriotia Ontario, N0N 1R0  
Phone: (519) 882-0032 Fax: (519) 882-2233

DRAWING NAME: Charles Shepley Drain Plan  
PROJECT No: 2019-1021



APPROVED	SCALE	PLAN
M. GERRITS	1:10,000	
CHECKED		
J. WARNER	NO. REVISIONS	DATE BY
	3 COR REVISIONS	APRIL 6, 2021 MG
DRAWN	2 FINAL REPORT	JAN.18, 2021 MG
B. VAN RUITENBURG	1 DRAFT REPORT	DEC.16, 2020 MG

**TOWN of AMHERSTBURG**  
CHARLES SHEPLEY DRAIN  
PLAN


**1**  
**OF 9**

Last Update: May 4, 2021


**GENERAL NOTES**

1. BENCHMARK No.1 ELEV. 185.99  
 TOP NORTH END OF EXISTING 2200mmØ  
 CSP AT STATION 0+131  
 CULVERT #1


BENCHMARK No.2 ELEV. 186.837  
 TOP NORTH END OF EXISTING HEADWALL  
 AT STATION 0+446  
 CULVERT #2



**OUTLET DETAIL**  
 NTS



**TYPICAL DRAIN CROSS SECTION**  
 (STA. 0+000 TO 1+265)  
 NTS



4218 Oil Heritage Road  
 Petrolia Ontario, N0N 1R0  
 Phone: (519) 882-0032 Fax: (519) 882-2233

DRAWING NAME:  
 Charles Shepley Drain Profile1

PROJECT No.  
 2019-1021

APPROVED	M. GERRITS	NO.	2	REVISIONS	FINAL REPORT	DATE	JAN.18, 2021	BY	MG
CHECKED	J. WARNER	NO.	1	REVISIONS	DRAFT REPORT	DATE	DEC.16, 2020	BY	MG
DRAWN	B. VAN RUITENBURG	SCALE: 1:2,000		0 20 40 60m					


**TOWN of AMHERSTBURG**  
 CHARLES SHEPLEY MAIN DRAIN  
 PROFILE

Last Updated: January 15, 2021


**GENERAL NOTES**

1. BENCHMARK No.3 ELEV. 186.99  
 TOP SOUTH END OF EXISTING 1200mm $\phi$   
 CSP AT STATION 1+157  
 CULVERT #3


BENCHMARK No.4 ELEV. 186.99  
 TOP SOUTH END OF EXISTING 1200mm $\phi$   
 CSP AT STATION 1+239  
 CULVERT #4



TYPICAL DRAIN CROSS SECTION  
 (STA. 1+265 TO 3+780)  
 NTS



TYPICAL DRAIN CROSS SECTION  
 (STA. 0+000 TO 1+265)  
 NTS



4218 Oil Heritage Road  
 Petrolia Ontario, N0H 1R0  
 Phone: (519) 882-0032 Fax: (519) 882-2233

DRAWING NAME:  
 Charles Shepley Drain Profile2

PROJECT No.  
 2019-1021

APPROVED	M. GERRITS	NO.	REVISIONS	DATE	BY
CHECKED	J. WARNER	2	FINAL REPORT	JAN.18, 2021	MG
DRAWN	B. VAN RUITENBURG	1	DRAFT REPORT	DEC.16, 2020	MG
		SCALE: 1:2,000			
		0 20 40 60m			


TOWN of AMHERSTBURG  
 CHARLES SHEPLEY MAIN DRAIN  
 PROFILE

3  
 OF 9




**GENERAL NOTES**

- 1. BENCHMARK No.5 ELEV. 187.82  
TOP NORTH END OF EXISTING 2200mmØ  
CSP AT STATION 1+799  
CULVERT #5



**TYPICAL DRAIN CROSS SECTION**  
(STA. 1+265 TO 3+780)  
NTS



4218 Oil Heritage Road  
Petroha Ontario, N0M 1R0  
Phone: (519) 882-0032 Fax: (519) 882-2233

DRAWING NAME:  
Charles Shepley Drain Profile3

PROJECT No.  
2019-1021

APPROVED	NO.	REVISIONS	DATE	BY
M. GERRITS	2	FINAL REPORT	JAN.18, 2021	MG
CHECKED	1	DRAFT REPORT	DEC.16, 2020	MG
J. WARNER				
DRAWN				
B. VAN RUITENBURG				

SCALE: 1:2,000  
0 20 40 60m


**TOWN of AMHERSTBURG**  
CHARLES SHEPLEY MAIN DRAIN  
PROFILE

4  
OF 9


Last Updated: January 15, 2021

**GENERAL NOTES**

- BENCHMARK No.6 ELEV. 188.62  
TOP EAST END OF EXISTING 1200mmØ  
CSP AT STATION 2+744  
CULVERT #6



**TYPICAL DRAIN CROSS SECTION**  
(STA. 1+265 TO 3+780)  
NTS



4218 Oil Heritage Road  
Petrolia Ontario, N0N 1R0  
Phone: (519) 882-0032 Fax: (519) 882-2233

DRAWING NAME:  
Charles Shepley Drain Profile4

PROJECT No.  
2019-1021

APPROVED	NO.	REVISIONS	DATE	BY
M. GERRITS	2	FINAL REPORT	JAN.18, 2021	MG
CHECKED	1	DRAFT REPORT	DEC.16, 2020	MG
J. WARNER				
DRAWN	SCALE: 1: 2,000			
B. VAN RUITENBURG	0 20 40 60m			


**TOWN of AMHERSTBURG**  
CHARLES SHEPLEY MAIN DRAIN  
PROFILE

**5**  
**OF 9**


**GENERAL NOTES**

1. BENCHMARK No.7 ELEV. 188.11  
 INVERT OF EAST END OF EXISTING 900mm $\phi$   
 CSP AT STATION 3+021  
 CULVERT #7

BENCHMARK No.8 ELEV. 188.13  
 TOP WEST END OF EXISTING 900mm $\phi$   
 CSP AT STATION 3+391  
 CULVERT #8



TYPICAL DRAIN CROSS SECTION  
 (STA. 1+265 TO 3+780)  
 NTS



4218 Oil Heritage Road  
 Petrolia Ontario, N0N 1R0  
 Phone: (519) 882-0032 Fax: (519) 882-2233

DRAWING NAME:  
 Charles Shepley Drain Profiles

PROJECT No.  
 2019-1021

APPROVED	NO.	REVISIONS	DATE	BY
M. GERRITS	2	FINAL REPORT	JAN.18, 2021	MG
CHECKED	1	DRAFT REPORT	DEC.16, 2020	MG
J. WARNER				
DRAWN	SCALE: 1:2,000			
B. VAN RUITENBURG	0 20 40 60m			


TOWN of AMHERSTBURG  
 CHARLES SHEPLEY MAIN DRAIN  
 PROFILE

6  
 OF 9




**GENERAL NOTES**

- 1. BENCHMARK No.8 ELEV. 188.13
- TOP WEST END OF EXISTING 900mmØ
- CSP AT STATION 3+391
- CULVERT #8



**TYPICAL DRAIN CROSS SECTION  
(STA. 1+265 TO 3+780)**  
NTS



4218 Oil Heritage Road  
Petrolia Ontario, N0N 1R0  
Phone: (519) 882-0032 Fax: (519) 882-2233

DRAWING NAME: Charles Shepley Drain Profile6  
PROJECT No. 2019-1021

APPROVED	NO.	REVISIONS	DATE	BY
M. GERRITS	2	FINAL REPORT	JAN.18, 2021	MG
CHECKED	1	DRAFT REPORT	DEC.16, 2020	MG
J. WARNER				
DRAWN	SCALE: 1: 2,000			
B. VAN RUITENBURG	0 20 40 60m			

**TOWN of AMHERSTBURG**  
**CHARLES SHEPLEY MAIN DRAIN**  
**PROFILE**


**7**  
**OF 9**

Last Updated: January 15, 2021


**GENERAL NOTES**

1. BENCHMARK No.9 ELEV. 186.87  
 TOP WEST END OF EXISTING 760mmØ  
 CSP AT STATION 4+388  
 CULVERT #9

BENCHMARK No.10 ELEV. 186.98  
 TOP NORTH END OF EXISTING 450mmØ  
 HDPE AT STATION 4+678  
 CULVERT #10



**TYPICAL DRAIN CROSS SECTION**  
 (STA. 4+000 TO 4+990)  
 NTS



4218 Oil Heritage Road  
 Petrolia Ontario, N0N 1R0  
 Phone: (519) 882-0032 Fax: (519) 882-2233

DRAWING NAME:  
 Charles Shepley Branch Drain Profile1

PROJECT No.  
 2019-1021

APPROVED	M. GERRITS	NO.	REVISIONS	DATE	BY
CHECKED	J. WARNER	2	FINAL REPORT	JAN.18, 2021	MG
DRAWN	B. VAN RUITENBURG	1	DRAFT REPORT	DEC.16, 2020	MG

SCALE: 1:2,000  
 0 20 40 60m

**TOWN of AMHERSTBURG**  
 CHARLES SHEPLEY BRANCH DRAIN  
 PROFILE




DRWING NAME: Charles Shepley Branch Drain Profiles  
 PROJECT No. 2019-1021  
 4218 Oil Heritage Road  
 Petrolia Ontario, N0N 1R0  
 Phone: (519) 882-0032 Fax: (519) 882-2233


APPROVED	M. GERRITS	
CHECKED	J. WARNER	
DRWING	B. VAN RUITENBURG	
NO.	REVISIONS	DATE
2	FINAL REPORT	JAN.18, 2021
1	DRAFT REPORT	DEC.16, 2020
SCALE: 1:2,000		
0 20 40 60m		

# TOWN of AMHERSTBURG CHARLES SHEPLEY BRANCH DRAIN PROFILE AND DETAILS

9 OF 9



- GENERAL NOTES**
- BENCHMARK NO.11 ELEV. 187.22  
 TOP WEST END OF EXISTING 400mm $\phi$   
 CSP AT STATION 4+980  
 CULVERT #11  
 ALL GRANULARS COMPACTED TO 98%  
 MODIFIED PROCTOR DENSITY



TYPICAL DRAIN CROSS SECTION  
 (STA. 4+000 TO 4+990)

